

SECTION 01 11 00

SUMMARY OF WORK

01/08

PART 1 GENERAL

1.1 SUBMITTALS

Government approval is required for submittals with a "G" designation; submittals not having a "G" designation are for information only. When used, a designation following the "G" designation identifies the office that will review the submittal for the Government. The following shall be submitted in accordance with Section 01 33 00 SUBMITTAL PROCEDURES:

SD-01 Preconstruction Submittals

Upon receipt of Government Furnished Equipment, the Contractor shall submit records in accordance with paragraph entitled, "Government Furnished Property," of this section.

Submit the following items to the Contracting Officer:

Utility Outage Requests; G
Utility Connection Requests; G

1.2 WORK COVERED BY CONTRACT DOCUMENTS

1.2.1 Project Description

The work includes installing a new ultra high speed fire suppression system in the indicated high hazard zones in the seven (7) explosive production bays and an overhead wet pipe sprinkler system in eight (8) bays in Building 1206. The project includes a new fire pump located remotely and the associated piping and electrical upgrades to support the new system, and incidental related work, as indicated in the contract documents.

1.2.2 Location

The work shall be located at Building 1206, Eglin AFB, as indicated on the drawings. Building 1206 is located in the High Explosive Research and Development (HERD) complex. The HERD complex is a secure area and will require escorts. The exact location will be shown by the Contracting Officer.

1.3 EXISTING WORK

In addition to "FAR 52.236-9, Protection of Existing Vegetation, Structures, Equipment, Utilities, and Improvements":

- a. Remove or alter existing work in such a manner as to prevent injury or damage to any portions of the existing work which remain.
- b. Restore portions of existing work which have been altered during construction operations to match existing or adjoining work, as approved by the Contracting Officer. At the completion of operations, existing work shall be in a condition equal to or better than that which existed before new work started.

1.4 ON-SITE PERMITS

1.4.1 Utility Outage Requests and Utility Connection Requests

Notify the Contracting Officer at least 48 hours prior to starting excavation work. Contractor is responsible for marking and verifying all utilities not marked.

The Contractor shall verify the elevations of existing piping, utilities, and any type of underground obstruction not indicated or specified to be removed. But indicated in locations to be transversed by piping, ducts, and other work to be installed. Verify elevations before installing new work closer than nearest manhole or other structure at which an adjustment in grade can be made.

Work shall be scheduled to hold outages to a minimum.

Utility outages and connections required during the prosecution of work that affect existing systems shall be arranged for at the convenience of the Government and shall be scheduled outside the regular working hours or on weekends.

Requests for utility outages and connections shall be made in writing to the Contracting Officer at least 10 work days in advance of the time required. Each request shall state the system involved, area involved, approximate duration of outage, and the nature of work involved.

1.5 LOCATION OF UNDERGROUND FACILITIES

The Contractor shall obtain a fully approved Form 103 "Work Clearance Form" prior to beginning work. Verify elevations before installing new work closer than nearest manhole or other structure at which an adjustment in grade can be made.

1.5.1 Notification Prior to Excavation

Notify the Contracting Officer at least 48 hours prior to starting excavation work.

1.6 SALVAGE MATERIAL AND EQUIPMENT

Items designated by the Contracting Officer to be salvaged shall remain the property of the Government.

The salvaged property shall be segregated, itemized, delivered, and off-loaded at the Government designated storage area.

Contractor shall maintain property control records for material or equipment designated as salvage. Contractor's system of property control may be used if approved by the Contracting Officer. Contractor shall be responsible for storage and protection of salvaged materials and equipment until disposition by the Contracting Officer.

PART 2 PRODUCTS

Not used.

REPLACE FIRE ALARM AND FIRE SUPPRESSION, BLDG. 1206
EGLIN AFB, FLORIDA

FTFA 15-1112
15AT

PART 3 EXECUTION

Not used.

-- End of Section --