

BID 24-028
Pensacola International Airport
Tippin Avenue Remote Parking Lot Project
QUANTITY SHEET

Company Name: _____

(page 1)

No.	Category	Qty	Units	Unit Price	Total Cost
1	Mobilization and Demobilization	1	LS		
2	Erosion Control* (incl. silt fence, outlet protection, and haybales)	1	LS		
3	Demolition/Layout (to include all demolition and clearing/grubbing)	1	LS		
4	Maintenance of Traffic (FDOT Standards)	1	LS		
5	Site, Grading, and Earthwork	1	LS		
6	Pond Excavation (Compacted in Place) Haul Off - Quantity Verified Before & After Topo Survey	6495	CY		
7	Sand Chimney Per Plans	1	LS		
8	12" SDR 26 PVC	16	LF		
9	18" Class III RCP	345	LF		
10	14"X23" Class III ERCP	197	LF		
11	19"X30" Class III ERCP	247	LF		
12	City Type A-1 Curb Inlet	1	EA		
13	FDOT TYPE V Inlet	1	EA		
14	6'x4' Ditch Bottom Inlet	1	EA		
15	FDOT TYPE C Ditch Bottom Inlet	1	EA		
16	FDOT TYPE 6 Curb Inlet	2	EA		
17	24" MES w/ Rip Rap Per Detail	1	EA		
18	4' Dia. Manhole Per Detail	1	EA		
19	Type C Curb and Gutter	3,473	LF		
20	Concrete Ribbon Curb	570	LF		

THIS FORM MUST BE INCLUDED IN SUBMITTAL.

BID 24-028
Pensacola International Airport
Tippin Avenue Remote Parking Lot Project
QUANTITY SHEET

Company Name: _____

(page 2)

No.	Category	Qty	Units	Unit Price	Total Cost
21	Concrete Valley Gutter	117	LF		
22	9' (O.D.) Wide x 6" Thick Concrete Flume with Rip Rap Per Detail	1	LS		
23	5' (O.D.) Wide x 6" Thick Concrete Flume with Rip Rap Per Detail	1	LS		
24	Raise Monitoring Wells To Be Flush with Proposed Grade	7	EA		
25	Restore Tippin Ave. Curb and Gutter (Match Existing)	90	LS		
26	Restore Tippin Ave. 4" Thick Concrete Sidewalk	140	SY		
27	Mill 1.5" Asphalt	705	SY		
28	1.5" SP 12.5 Asphalt	19,236	SY		
29	6" Graded Aggregate Base	18,531	SY		
30	18" Compacted Subgrade	18,531	SY		
31	Signage/Striping (Thermoplastic) (Including All Wheel Stops and ADA Spaces)	1	LS		
32	Landscaping Per Plans	1	LS		
33	Irrigation (Design Build)	1	LS		
34	365 Landscaping Establishment Period Maintenance	1	LS		
35	Decorative Ameristar Montage Plus Fence - Swing Gate	3	LS		
36	Decorative Ameristar Montage Plus Fence	2,035	LF		
37	Two Side by Side 5'x10' PreFab Bus Shelter by Panel Built, Inc. Set on 4" Thick Concrete Slab (Design Build)	1	LS		
38	Electrical and Lighting (Design Build)	1	LS		
39	Security Call Box (Design Build)	5	EA		

THIS FORM MUST BE INCLUDED IN SUBMITTAL.

BID 24-028
Pensacola International Airport
Tippin Avenue Remote Parking Lot Project
QUANTITY SHEET

(page 3)

No.	Category	Qty	Units	Unit Price	Total Cost
40	Install all Ticket Dispensers, Exit Stations, Electrical, Detection Loops, Swing Arm, etc. as Depicted on Sheet D-3 - Coordinate with Republic Parking System.	1	LS		
41	EV Charging Stations (Design Build)	7	EA		
BASE BID TOTAL					

***NOTES**

1. Bid shall include all associated earthwork and necessary back-sloping as determined by the City of Pensacola
2. This bid proposal contains line items which may not be called out on the plans. Such items have been included to address potential unforeseen conditions.
3. The City of Pensacola reserves the right to move forward with or opt out of bid alternates in any order.

Bidder: _____
Name of Company (Please Print)

Date: _____

By: _____
Authorized Representative (Please Print)

Signature: _____

Title: _____

THIS FORM MUST BE INCLUDED IN SUBMITTAL.