




48 HOURS
BEFORE YOU DIG
CALL SUNSHINE ONE
1-800-432-4770
www.callsunshine.com

NOT FOR CONSTRUCTION

PROJECT NO.	24-812
SCALE	1"=20'
DATE	12/2024
DATE	12/2024
PROJECT NO.	24-812
SCALE	1"=20'
DATE	12/2024
DATE	12/2024

OKALOOSA COUNTY
TAX COLLECTOR'S OFFICE
DRAINAGE PLAN



Seaside Engineering And Surveying, LLC
655 Highway 19 N
Baker, FL 32531
Ph: (850) 950-9612
Fax: (850) 398-8812

DATE:	03/10/25
BY:	M.C.G.
DATE:	03/10/25
BY:	M.C.G.
DATE:	03/10/25
BY:	M.C.G.

REVISIONS	DATE	DESCRIPTION

LEGEND
EXISTING GRADE CONTOUR (AT 5' INTERVAL)
EXISTING GRADE CONTOUR (AT 1' INTERVAL)
FINISHED GRADE CONTOUR
SILT FENCE LOCATION
SECTION LOCATION WITH SECTION NUMBER

NOTES

1. TOPOGRAPHIC SURVEY BY SEAS ENGINEERING AND SURVEYING, LLC, PERFORMED MAY 2024. ELEVATIONS SHOWN HEREON ARE REFERENCED TO MADD88.
2. BENCHMARKS: AS SHOWN
3. CONTOUR INTERVAL = ONE FOOT
4. PROPOSED CONTOURS AND SPOT ELEVATIONS REPRESENT FINISHED GRADE.
5. SPOT ELEVATIONS ALONG CURB REPRESENT FINISHED GRADE AT BACK OF CURB UNLESS OTHERWISE LABELED.
6. STORMWATER RUNOFF, SEDIMENT, AND EROSION SHALL BE CONTROLLED DURING ALL PHASES OF CONSTRUCTION.
7. MATCH EXISTING EDGE OF PAVEMENT GRADE WHEREVER NEW PAVEMENT EDGE MEETS THE EXISTING EDGE.
8. CONTRACTOR SHALL PROVIDE SOLID SODDING WITHIN THE RETENTION BASINS AND ALL OTHER CLEARED AND GRUBBED AREAS WITH SLOPES OF 3:1 OR STEEPER.
9. PRIOR TO FINAL APPROVAL BY CITY OF CRESTVIEW PUBLIC WORKS, THE CONTRACTOR SHALL SUBMIT A DETAILED EROSION CONTROL PLAN, SPECIFICALLY ADDRESSING EROSION, GRADING, RUNOFF CONVEYANCE AND RETENTION BASIN RECOVERY TIME. THIS PLAN WILL BE VERIFIED.
10. ANY EXISTING VEGETATION OUTSIDE THE LIMITS OF CONSTRUCTION SHALL BE RETAINED AND WILL MEET THE REQUIREMENTS OF THE CITY OF CRESTVIEW LAND DEVELOPMENT CODE.
11. ROOF DOWNSPOUTS SHALL BE CONNECTED TO YARD DRAINAGE SYSTEM.

