
# PORT FACILITIES FOR

### THE CITY OF PENSACOLA

PENSACOLA, FLORIDA

### PAVING & RAIL REHABILITATION PROJECT

BID NO. 26-001 OCTOBER 2025





VICINITY MAP

LOCATION MAP

NTS



			PROJECT MANAGER	HAC
			DESIGNED BY	HAC
			CHECKED BY	HAC
			DRAWN BY	PEM
			-	
			-	
			-	
Α	OCT. 2025	ISSUED FOR BID	-	
ISSUE	DATE	DESCRIPTION	PROJECT NUMBER	10419078

ISSUED FOR BID NOT FOR CONSTRUCTION



PORT OF PENSACOLA PAVING & RAIL REHABILITION PROJECT

PROJECT COVER SHEET & VICINITY MAP

1" 2" FILEN

FILENAME G1.DWG

SCALE AS SHOWN

<sub>ΕΤ</sub> **G1** 

G1 G2	DRAWING TYPE	DRAWING TITLE	
			INCLUDE
G2	GENERAL	PROJECT COVER SHEET & VICINITY MAP	Х
	GENERAL	PROJECT DRAWING INDEX	X
G3	GENERAL	PROJECT GENERAL NOTES	X
G100	GENERAL	OVERALL SITE PLAN	X
G200	GENERAL	EXISTING CONDITIONS PLAN (1 OF 5)	X
G201	GENERAL	EXISTING CONDITIONS PLAN (2 OF 5)	X
G202	GENERAL	EXISTING CONDITIONS PLAN (3 OF 5)	X
G203	GENERAL	EXISTING CONDITIONS PLAN (4 OF 5)	X
G204	GENERAL	EXISTING CONDITIONS PLAN (5 OF 5)	X
B100	GENERAL	SOIL BORINGS OVERALL SITE PLAN	X
B101	GENERAL	BORING LOGS (1 OF 4)	X
B102	GENERAL	BORING LOGS (2 OF 4)	X
B103	GENERAL	BORING LOGS (3 OF 4)	X
B104	GENERAL	BORING LOGS (4 OF 4)	X
X200	DEMO	DEMOLITION PLAN (1 OF 5)	X
X201	DEMO	DEMOLITION PLAN (2 OF 5)  DEMOLITION PLAN (3 OF 5)	X
X202	DEMO	DEMOLITION PLAN (3 OF 5)  DEMOLITION PLAN (4 OF 5)	X
X203	DEMO DEMO	DEMOLITION PLAN (4 OF 5)  DEMOLITION PLAN (5 OF 5)	X
X204 W200	WATER	NEW WATER LINES LOCATION PLAN (1 OF 5)	X
W200	WATER	NEW WATER LINES LOCATION PLAN (2 OF 5)	X
W201	WATER	NEW WATER LINES LOCATION PLAN (3 OF 5)	X
W202	WATER	NEW WATER LINES LOCATION PLAN (4 OF 5)	X
W203	WATER	NEW WATER LINES LOCATION PLAN (5 OF 5)	X
W501	WATER	NEW WATER LINES SECTIONS & DETAILS	X
W502	WATER	NEW WATER LINES SECTIONS & DETAILS	X
W503	WATER	NEW WATER LINES SECTIONS & DETAILS	X
W504	WATER	NEW WATER LINES SECTIONS & DETAILS	X
W505	WATER	NEW WATER LINES SECTIONS & DETAILS	X
D200	DRAINAGE	DRAINAGE SYSTEM SITE PLAN (1 OF 2)	X
D201	DRAINAGE	DRAINAGE SYSTEM SITE PLAN (2 OF 2)	X
D500	DRAINAGE	DRAINAGE SYSTEM SECTIONS & DETAILS	X
R200	RAIL	RAIL ENLARGEMENT PLAN (1 OF 3)	Х
R201	RAIL	RAIL ENLARGEMENT PLAN (2 OF 3)	X
R202	RAIL	RAIL ENLARGEMENT PLAN (3 OF 3)	Х
R300	RAIL	TRACK 1 PROFILE	Х
R301	RAIL	TRACK 2 PROFILE	Х
R302	RAIL	TRACK 3 PROFILE	X
R303	RAIL	TRACK 4 PROFILE	X
R304	RAIL	TRACK 5 PROFILE	X
R305	RAIL	TRACK 6 PROFILE	X
R306	RAIL	TRACK 7 PROFILE	X
R400	RAIL	GEOMETERY TABLE	X
R401	RAIL	GEOMETERY TABLE	X
R500	RAIL	RAIL DETAIL	X
P200	PAVING	PAVING BASE BID (1 OF 5)	X
P201	PAVING	PAVING BASE BID (2 OF 5)	X
P202	PAVING	PAVING BASE BID (3 OF 5)	X
P203	PAVING	PAVING BASE BID (4 OF 5)	X
P204	PAVING	PAVING BASE BID (5 OF 5)	X
P205	PAVING	PAVING SITE PLAN - ADDITIVE ALTERNATIVES (1 OF 5)	X
P206	PAVING	PAVING SITE PLAN - ADDITIVE ALTERNATIVES (2 OF 5)	X
P207	PAVING	PAVING SITE PLAN - ADDITIVE ALTERNATIVES (3 OF 5)	X
P208	PAVING	PAVING SITE PLAN - ADDITIVE ALTERNATIVES (4 OF 5)	X
P209	PAVING	PAVING SITE PLAN - ADDITIVE ALTERNATIVES (5 OF 5)	X
P500	PAVING	DETAILED ENLARGEMENT PLAN - WAREHOUSE 1 GARAGE DOOR RAMP	X
P501	PAVING	PAVING DETAILS	X
S500	STRUCTURAL	PAVING AND WATER VAULT STRUCTURES SECTIONS & DETAILS	X
S501	STRUCTURAL	BERTH 6 RETAINING WALL EXPANSION JOINT REPAIR SECTIONS & DETAILS	X
S502	STRUCTURAL	BERTH 3 & 5 EXPANSION JOINT REPAIR SECTIONS & DETAILS	X
S503	STRUCTURAL	BERTH 3 & 5 EXPANSION JOINT REPAIR SECTIONS & DETAILS	X
S504	STRUCTURAL	PIPE PENETRATION DETAIL	X
S505	STRUCTURAL	PAVING AND WATER VAULT STRUCTURES SECTIONS & DETAILS	X

HDR Engineering, Inc.
25 W. Cedar Street, Suite 200
Pensacola, FL 32502
Certificate of Authorization No. 4213

| PROJECT MANAGER | HAC | DESIGNED BY | HAC | CHECKED BY | HAC | DRAWN BY | PEM | | PEM |

ISSUED FOR BID
NOT FOR CONSTRUCTION



### PORT OF PENSACOLA PAVING & RAIL REHABILITION PROJECT

#### PROJECT DRAWING INDEX

) 1" 2"	FILENA
	SCA

FILENAME	G2.DWG
SCALE	AS SHOWN

€T **G2** 

Tuesday, October 07, 2025 — 7:46am Plotted by: PMCINTIRE C:\pwworking\east01\d4343785\G2.dwg Layout Name: Layout1

#### GENERAL REQUIREMENTS

- THE DETAILED REQUIREMENTS FOR ALL ITEMS DESCRIBED IN THE GENERAL NOTES ARE CONTAINED IN THE SPECIFICATIONS.
- CONTRACTOR SHALL NOT COMMENCE ANY CONSTRUCTION OPERATION UNTIL THE CONTRACTOR HAS VERIFIED THAT CONSTRUCTION / ENVIRONMENTAL PERMITS FOR THIS PROJECT HAVE BEEN ACQUIRED.
- DESIGN AND CONSTRUCTION SHALL COMPLY WITH ALL APPLICABLE STATE AND LOCAL CODES AND STANDARDS, THE PROJECT SPECIFICATIONS AND PROJECT DRAWINGS. NOTES PROVIDED IN DRAWINGS SHALL TAKE PRECEDENCE OVER PROJECT SPECIFICATION DOCUMENTS. SPECIFIC NOTES ON DETAIL DRAWINGS TAKE PRECEDENCE OVER DRAWING XX-XX. STATE AND LOCAL CODES SHALL TAKE PRECEDENCE OVER PROJECT SPECIFICATIONS AND NOTES ON DRAWINGS, CONTRACTOR SHALL NOTIFY OWNER IMMEDIATELY OF ANY CONFLICTS BETWEEN STATE AND LOCAL CODES, PROJECT SPECIFICATIONS AND PROJECT DRAWINGS PRIOR TO ANY CONSTRUCTION.
- CONTRACTOR SHALL FIELD CHECK AND VERIFY ALL ELEVATIONS, COORDINATES, DIMENSIONS, EXISTING CONDITIONS, AND INFORMATION INDICATED ON THE CONTRACT DOCUMENTS PRIOR TO COMMENCEMENT OF SITE WORK. THE OWNER SHALL BE NOTIFIED IMMEDIATELY OF ANY DISCREPANCIES FOUND ON THE CONTRACT DOCUMENTS OR FOUND TO EXIST BETWEEN THE FIELD CONDITIONS AND THE CONTRACT DOCUMENTS. THE CONTRACTOR SHALL TAKE CORRECTIVE ACTION AS DIRECTED BY THE OWNER.
- CONTRACTOR SHALL SUBMIT STORM WATER POLLUTION PREVENTION PLAN (SW3P) TO XXX. CONSTRUCTION ACTIVITY MAY NOT COMMENCE UNIT SW3P IS APPROVED BY XXXX. REFER TO SPECIFICATION SECTION XX XX XX - TEMPORARY STORMWATER POLLUTION CONTROL FOR ADDITIONAL REQUIREMENTS.
- CONTRACTOR SHALL PROVIDE AND MAINTAIN ALL TRAFFIC CONTROL DEVICES DURING THE COURSE OF THE CONSTRUCTION PERIOD.
- CONTRACTOR TO COORDINATE WITH LOCAL PILOT AND PORT OF PENSACOLA ON MARINE TRAFFIC/MOVEMENTS SCHEDULES WHICH MAY AFFECT CONSTRUCTION WORKS. THE CONTRACTOR WILL NOT BE GIVEN DELAY PAYMENT ALLOWANCE FOR MARINE TRAFFIC/MOVEMENTS THAT AFFECT CONSTRUCTION.
- THIS PROJECT IS SUBJECT TO ENVIRONMENTAL PROTECTION AGENCY (EPA) NATIONAL POLLUTION DISCHARGE ELIMINATION SYSTEM (NPDES) CONSTRUCTION STORM WATER DISCHARGE REGULATIONS AND REQUIREMENTS. THE CONTRACTOR SHALL EXECUTE A NOTICE OF INTENT AND IMPLEMENT THE POLLUTION PREVENTION PLAN PER USACE PERMIT. COMPLY WITH ALL REPORTING AND INSPECTION REQUIREMENTS SET FORTH IN THE NPDES REGULATION.
- ALL EXISTING ROADWAYS AND OTHER FEATURES WHICH ARE DAMAGED BY THE CONTRACTOR SHALL BE REPAIRED AT THE CONTRACTOR'S EXPENSE TO THE SATISFACTION OF THE OWNER.
- 10. CONTRACTOR SHALL MAINTAIN ALL REGULATORY AND WARNING SIGNS DURING THE CONSTRUCTION PERIOD.
- 11. CONTRACTOR SHALL SUBMIT TO OWNER ALL MATERIAL CERTIFICATES PRIOR TO FABRICATION.
- 12. CONTRACTOR SHALL CONDUCT HIS OPERATIONS SO AS TO NOT INTERFERE WITH, OR BE DETRIMENTAL TO VESSEL AND VEHICULAR TRAFFIC AND THE DAILY OPERATION OF THE OWNER DURING THE COURSE OF THE WORK.
- 13. ALL EXISTING FEATURES OF THE PROJECT SITE WHICH ARE DAMAGED BY THE CONTRACTOR DURING HIS OPERATIONS SHALL BE REPAIRED AT THE CONTRACTOR'S EXPENSE TO THE SATISFACTION OF THE OWNER.
- 14. WORKER SAFETY IN EXCAVATIONS AND TRENCHES SHALL BE PROVIDED BY THE CONTRACTOR IN ACCORDANCE WITH OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION (OSHA) STANDARDS, 29 CFR 1926, SUBPART P - EXCAVATIONS, TRENCHING, AND SHORING. CONTRACTOR SHALL ALSO COMPLY WITH ALL APPLICABLE STATE AND LOCAL REQUIREMENTS. A COPY OF THE GEOTECHNICAL REPORT CAN BE OBTAINED FROM THE OWNER FOR USE BY THE CONTRACTOR IN THE DESIGN OF THE TRENCH SAFETY SYSTEM.
- 15. THE CONTRACTOR SHALL PERFORM CONSTRUCTION ACTIVITIES IN ACCORDANCE WITH OSHA AND CONTRACT DOCUMENTS.
- 16. CONTRACTOR, SUBCONTRACTORS AND OTHER CONTRACTED ENTITIES SHALL SUCCESSFULLY COMPLETE ALL THE TRAINING COURSES AND REQUIREMENTS REQUIRED BY OWNER IN ORDER TO ACCESS THE PROJECT SITE AND CARRY OUT THE CONTRACTED WORK. CONTRACTOR SHALL POSSESS ALL THE REQUIRED IDENTIFICATION DOCUMENTS AND SHALL ACCESS THE PROJECT SITE THROUGH OWNER SECURITY CHECK POINT AND FOLLOW OWNER'S CHECK-IN/-OUT PROCEDURE ON A DAILY BASIS. THE IDENTIFICATION DOCUMENTS INCLUDE, AS A MINIMUM, VALID TRANSPORTATION WORKER IDENTIFICATION CREDENTIAL (TWIC®) CARD AND VALID DRIVER'S LICENSE.
- 17. CONTACT OWNER FOR TRAINING INFORMATION AND PARKING REQUIREMENTS.

#### SHOP DRAWINGS

- THE CONTRACTOR SHALL FIELD VERIFY ALL DIMENSIONS AND ELEVATIONS SHOWN ON THE DRAWINGS, PRIOR TO PREPARATION OF SHOP DRAWINGS.
- SHOP DRAWINGS SHALL BE SUBMITTED TO AND APPROVED BY THE ENGINEER BEFORE PURCHASE OF ANY MATERIALS OR START OF FABRICATION
- THE USE OF REPRODUCTIONS OF THESE CONTRACT DRAWINGS BY ANY CONTRACTOR, SUBCONTRACTOR, ERECTOR, FABRICATOR, OR MATERIAL SUPPLIER IN LIEU OF PREPARATION OF SHOP DRAWINGS IS PROHIBITED.

#### HORIZONTAL AND VERTICAL CONTROL

- 1. TOPOGRAPHIC SURVEY WAS PERFORMED BY S.A.M, INC., UNDER JOB NO. 1024092970, DATED FEBRUARY 17, 2025.
- 2. HORIZONTAL COORDINATES SHOWN ARE STATE PLANE GRID, FLORIDA NORTH ZONE, IN U.S.
- 3. VERTICAL DATUM SHOWN ON THESE DRAWINGS REFERS TO NORTH AMERICAN VERTICAL DATUM 1988 (NAVD'88) IN U.S. FEET.
- 4. MONUMENTS USED FOR HORIZONTAL AND VERTICAL CONTROL ARE AS FOLLOWS: IRON REBAR W/DISK N 521'637.45' E 1,113,384.31' EL +5.541' **BRASS DISK IN CONCRETE** N 520,842.16' E 1,113,530.03' EL +6.707' **BRASS DISK IN CONCRETE** N 520,676.56' E 1,113,818.51' EL +10.364' BRASS DISK IN CONCRETE N 519,750.29' E 1,113,927.24' EL +11.737' BRASS DISK IN CONCRETE N 519,983.89' E 1,115,333.70' EL +10.979'
- DATUM CORRELATION TABLE:

	MLLW	NAVD '88
MEAN HIGHER HIGH WATER (MHHW)	+1.33'	+1.28'
MEAN HIGH WATER (MHW)	+1.26'	+1.21'
MEAN SEA LEVEL (MSL)	+0.73'	+0.68
MEAN TIDE LEVEL (MTL)	+0.69'	+0.64
MEAN LOW WATER (MLW)	+0.13'	+0.08'
NORTH AMERICAN VERTICAL DATUM 1988 (NAVD'88)	+0.05'	+0.00'
MEAN LOWER LOW WATER (MLLW)	+0.00'	-0.05'

WATER SURFACE RANGE BETWEEN MLLW AND MHHW REPRESENTS A NORMAL STATISTICAL WATER SURFACE RANGE. THE WATER SURFACE WILL ON OCCASION BE HIGHER OR LOWER THAN THIS RANGE.

#### **DEMOLITION AND SALVAGE**

- 1. THE CONTRACTOR SHALL REMOVE ALL EXISTING ABOVE SURFACE AND BURIED STRUCTURES ON THE SITE WHICH ARE REQUIRED TO ALLOW THE NEW CONSTRUCTION AS SHOWN. THE APPROXIMATE LOCATION AND EXTENT OF THESE STRUCTURES HAVE BEEN SHOWN ON THIS DRAWING.
- 2. DEMOLITION OF EXISTING FACILITIES UNLESS NOTED OTHERWISE SHALL BECOME THE PROPERTY OF THE CONTRACTOR AND SHALL BE DISPOSED OF LEGALLY AND PROPERLY
- 3. ALL CONCRETE, STEEL AND OTHER DEBRIS SHALL BE HAULED OFF SITE AND DISPOSED OF AT THE CONTRACTOR'S EXPENSE.

#### SITE WORK / EARTHWORK

- 1. FENCING WHICH IS REMOVED TO FACILITATE CONSTRUCTION SHALL BE REPLACED TO ORIGINAL OR BETTER CONDITION.
- 2. AREAS TO RECEIVE FILL SHALL BE EXCAVATED AND CLEARED TO REMOVE ALL VEGETATION.
- 3. ALL SUBGRADE AREAS SHALL BE COMPACTED TO 95% MODIFIED PROCTOR DENSITY BEFORE BASE IS PLACED.
- 4. COMPACT ALL BACKFILL TO 90% MODIFIED PROCTOR IN LIFTS NOT TO EXCEED 9-INCH IN
- 5. SUB-BASE MATERIAL SHALL BE COMPACTED TO 95% MODIFIED DENSITY TO A DEPTH OF
- 6. THE AREA SURROUNDING THE PAVING AND FOUNDATION AREAS SHALL BE GRADED IN SUCH A MANNER THAT RAINWATER DOES NOT POND AROUND THE AREA. RUNOFF SHALL BE DIVERTED AROUND THE FOUNDATION AREAS BY MEANS OF PROPER GRADING.
- 7. PAVEMENT TO BE REMOVED SHALL FIRST BE SAW-CUT THEN PAVEMENT AND BASE MATERIAL REMOVED TO A DEPTH REQUIRED TO ACCOMMODATE THE PAVING SECTION DEPTH INDICATED ON THE DRAWINGS. SUBGRADE SHALL BE COMPACTED AS SPECIFIED PRIOR TO THE PLACEMENT OF THE STONE BASE MATERIAL.

#### CONCRETE

- 1. BEFORE COMMENCING CONCRETE PLACEMENT, PERFORM THE FOLLOWING: SURFACES TO RECEIVE CONCRETE SHALL BE CLEAN AND FREE OF DELETERIOUS AND/OR ORGANIC MATERIALS, FROST, ICE AND MUD. FORMS SHALL BE IN PLACE, CLEANED, COATED AND ADEQUATELY SUPPORTED IN ACCORDANCE WITH THE APPROPRIATE SPECIFICATIONS."
- 2. ALL CONCRETE, EXCEPT AS NOTED, SHALL BE NORMAL WEIGHT CONCRETE AND SHALL HAVE A MINIMUM COMPRESSIVE STRENGTH OF 5000-PSI WHEN TESTED AT 28-DAYS. THE MAXIMUM WATER TO CEMENTITIOUS RATIO, BY WEIGHT SHALL BE 0.40. THE MIX DESIGN SHALL BE IN ACCORDANCE WITH THE TECHNICAL SPECIFICATION SECTION 03-30-03.
- A HIGH RANGE WATER REDUCING ADMIXTURE IN ACCORDANCE WITH THE SPECIFICATIONS SHALL BE USED IN ALL CONCRETE.
- 4. ALL CONCRETE WORK SHALL COMPLY WITH THE PROVISIONS AND RECOMMENDATIONS OF THE LATEST EDITIONS ACI 301 AND ACI 318, UNLESS OTHERWISE SPECIFIED.
- 5. ALL EXPOSED CORNERS SHALL BE PROVIDED WITH MINIMUM ¾-INCH CHAMFER, UNLESS OTHERWISE NOTED.
- CONCRETE FINISHES SHALL BE IN ACCORDANCE WITH THE SPECIFICATIONS. THE FOLLOWING EXPOSED FINISHED SURFACES SHALL HAVE THE DESIGNATED FINISH: SURFACE FINISH

MEDIUM BROOM

MEDIUM BROOM

**CONCRETE PAVING CURB AND GUTTER** 

- 7. APPLY TWO COATS OF SEALER TO ALL EXPOSED CONCRETE SURFACES (CAST-IN-PLACE AND PRECAST) AFTER CONSTRUCTION.
- CHANGES IN LOCATION, ADDITION OR OMISSION OF CONSTRUCTION JOINTS SHALL BE SUBJECT TO APPROVAL BY ENGINEER.
- 9. USE EPOXY CONCRETE BONDER PER SPECIFICATIONS AT ALL CONSTRUCTION JOINTS. WATER BLAST BEAMS BEFORE PLACING TOPPING.
- 10. PRIOR TO CASTING CONCRETE AGAINST HARDENED CONCRETE SURFACE, ROUGHEN THE EXISTING SURFACE TO FULL AMPLITUDE OF APPROXIMATELY 1/2-INCH. THOROUGHLY CLEAN THE HARDENED CONCRETE SURFACE OF ALL LOOSE MATERIALS, LAITANCE, DIRT, AND FOREIGN MATTER, AND SATURATE IT WITH WATER. THE CLEAN CONCRETE SURFACE SHOULD BE SATURATED, SURFACE DRY WITH NO FREE OR STANDING WATER AT THE TIME THE CONCRETE IS PLACED AGAINST IT.
- 11. ALL DETAILING, FABRICATION AND ERECTION OF REINFORCING STEEL SHALL CONFORM TO THE LATEST EDITION OF ACI DETAILING MANUAL SP-66.
- 12. ALL LOADS (INCLUDING VEHICULAR AND BACKFILL) SHALL BE KEPT AWAY FROM NEW CONCRETE FOR A MINIMUM OF 7-DAYS.
- 13. HORIZONTAL CONSTRUCTION JOINTS SHALL BE PERMITTED ONLY WHERE INDICATED ON THE DRAWINGS OR WITH PRIOR APPROVAL FROM ENGINEER.

#### REINFORCING STEEL

- 1. ALL REINFORCING STEEL SHALL CONFORM TO THE REQUIREMENTS OF ASTM A615 GRADE 60, UNLESS OTHERWISE NOTED.
- 2. ALL STIRRUPS SHALL BE ASTM A615 GRADE 60 WITH STANDARD 135-DEGREE HOOKS.
- WELDED WIRE FABRIC SHALL CONFORM TO ASTM A1064.
- 4. CLEAR COVER ON REINFORCING STEEL SHALL BE A MINIMUM OF 3-INCH, UNLESS OTHERWISE NOTED.
- 5. REINFORCING STEEL SHALL BE SUPPORTED USING ONLY PLASTIC CHAIRS OR BOLSTERS.
- 6. ALL REINFORCING BAR SCHEDULE DIMENSIONS GIVEN FOR REBAR ARE OUT TO OUT CENTER
- 7. DIMENSIONS TO REINFORCING STEEL ARE CENTERLINE DIMENSIONS UNLESS OTHERWISE NOTED.
- 8. MECHANICAL CONNECTORS MAY BE USED AT CONSTRUCTION JOINTS AND/OR IN LIEU OF LAP SPLICES. ALL MECHANICAL CONNECTORS SHALL BE SHOWN ON THE SHOP DRAWINGS AND SHALL CONFORM TO THE LATEST REVISIONS OF ACI 318.
- 9. THE INTENT OF THE REINFORCING SCHEDULE IS TO CLARIFY THE CONSTRUCTION DRAWINGS, BAR SHAPES AND PLACEMENT. CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND QUANTITIES PRIOR TO FABRICATION. CONTRACTOR SHALL BE RESPONSIBLE FOR ANY DISCREPANCIES BETWEEN SCHEDULES AND DRAWINGS.
- 10. EMBEDMENT AND SPLICE LENGTHS FOR REINFORCING STEEL SHALL COMPLY WITH THOSE SHOWN IN TABLE 1 AND TABLE 2.
- 11. REFER TO SPECIFICATIONS SECTION 03-30-00 FOR ADDITIONAL REQUIREMENTS.

TAE	TABLE 1 - MINIMUM SPLICE AND EMBEDMENT LENGTHS (INCHES)					
	CONCRETE STRENGTH = 5,000 PSI					
BAR SIZE NUMBER	MINIMUM EMBEDMENT LENGTH	TOP BARS EMBEDMENT LENGTH	MINIMUM SPLICE LENGTH	TOP BARS SPLICE LENGTH		
3	13	17	17	22		
4	17	22	22	29		
5	22	28	28	36		
6	26	33	33	43		
7	37	49	49	63		
8	43	55	56	72		
9	48	63	63	81		
10	54	70	70	91		
11	60	78	78	101		

TABLE	TABLE 2 - MINIMUM SPLICE AND EMBEDMENT LENGTHS (INCHES)					
	CONCRETE STRENGTH = 4,000 PSI					
BAR SIZE NUMBER	MINIMUM EMBEDMENT LENGTH	TOP BARS EMBEDMENT LENGTH	MINIMUM SPLICE LENGTH	TOP BARS SPLICE LENGTH		
3	15	19	19	24		
4	19	25	25	32		
5	24	31	31	40		
6	29	37	37	48		
7	42	54	54	70		
8	48	62	62	80		
9	54	70	70	91		
10	61	79	79	102		
11	67	87	87	113		

- A. WHERE BARS ARE OF DIFFERENT SIZE, THE LAP LENGTH SHALL BE BASED ON SMALLER BAR, UNLESS NOTED OTHERWISE
- B. THE CONTRACTOR SHALL DETERMINE ANY SPLICE LOCATIONS IN ADDITION TO THOSE SHOWN.
- SUBJECT TO SHOP DRAWING APPROVAL. C. TOP BARS ARE HORIZONTAL REINFORCEMENT SO PLACED THAT MORE THAN 12-INCH OF FRESH
- CONCRETE IS CAST IN THE MEMBER BELOW DEVELOPMENT LENGTH OR SPLICE.

25 W. Cedar Street, Suite 200 Pensacola, FL 32502 Certificate of Authorization No. 4213

PROJECT MANAGER | HAC DESIGNED BY HAC CHECKED BY HAC DRAWN BY PEM OCT. 2025 ISSUED FOR BID PROJECT NUMBER 10419078 ISSUE DATE DESCRIPTION

ISSUED FOR BID NOT FOR CONSTRUCTION




PORT OF PENSACOLA **PAVING & RAIL REHABILITION PROJECT** PROJECT GENERAL NOTES



SHEET FILENAME | G3.DWG SCALE AS SHOWN

G3



SHEET

G100

FILENAME G100.DWG

SCALE AS SHOWN

HDR Engineering, Inc. 25 W. Cedar Street, Suite 200

Certificate of Authorization No. 4213


A OCT. 2025

DATE

ISSUED FOR BID

DESCRIPTION


PROJECT NUMBER 10419078





PROJECT NUMBER 10419078 DESCRIPTION


0	1"	2" FILENA
		SC.

SHEET	G200.DWG	FILENAME
G20	AS SHOWN	SCALE









PORT ADMIN BLDG PORTSIDE PICKLE U-1 • OFFSHORE INLAND WAREHOUSE 1 WAREHOUSE 9 WAREHOUSE 10 PAINT воотн WAREHOUSE 8 R-7 R-10 WAREHOUSE 6 WAREHOUSE 5 ● U-7 SOIL BORING - OVERALL SITE PLAN SCALE:1"=150'-0"



**BORING NUMBER** DISCIPLINE LATITUDE LONGITUDE 1114061.72 PAVEMENT PAVEMENT PAVEMENT 1114024.28 1114189.56 PAVEMENT 1114374.09 PAVEMENT PAVEMENT 1114260.39 PAVEMENT PAVEMENT PAVEMENT 1114141.43 520475.79 P-11 1115230.85 PAVEMENT P-12 520135.59 1114363.45 PAVEMENT P-13 PAVEMENT 1114088.71 P-14 PAVEMENT 1114073.77 519828.74 520870.81 R-2 1114113.91 520829.32 RAIL R-3 1113913.67 520539.47 RAIL 520618.11 1114182.86 R-5 RAIL 1113951.40 520277.19 R-6 1114271.51 520282.16 RAIL R-7 RAIL 520086.36 RAIL 1114261.23 520140.29 1114713.03 R-10 1114049.26 RAIL 1114293.79 RAIL 1114153.57 521276.78 UTILITY U-2 UTILITY 1113877.82 520753.47 520541.09 1114377.96 UTILITY

**BORING LOCATION** 



			PROJECT MANAGER	HAC
			DESIGNED BY	HAC
			CHECKED BY	HAC
			DRAWN BY	PEM
			-	
			-	
			-	
Α	OCT. 2025	ISSUED FOR BID	-	
ISSUE	DATE	DESCRIPTION	PROJECT NUMBER	10419078

ISSUED FOR BID NOT FOR CONSTRUCTION




#### PORT OF PENSACOLA **PAVING & RAIL REHABILITION PROJECT**

1114985.18

1114726.99 1115272.59

SOIL BORING OVERALL SITE PLAN



UTILITY

UTILITY

UTILITY

UTILITY

U**-**5

FILENAME	B100.DWG
SCALE	AS SHOWN


520434.77

519909.09

519969.73

520255.66

B100



NOT FOR CONSTRUCTION

HDR Engineering, Inc. 25 W. Cedar Street, Suite 200

Certificate of Authorization No. 4213

A OCT. 2025

DATE

ISSUED FOR BID

DESCRIPTION

PROJECT NUMBER 10419078


Pensacola, FL 32502

SHEET

B101

FILENAME | B101.DWG

SCALE AS SHOWN



HDR Engineering, Inc. 25 W. Cedar Street, Suite 200 Pensacola, FL 32502

Certificate of Authorization No. 4213

CHECKED BY HAC DRAWN BY PEM A OCT. 2025 ISSUED FOR BID DESCRIPTION PROJECT NUMBER | 10419078


ISSUED FOR BID NOT FOR CONSTRUCTION




SOIL BORING LOGS (2 OF 4)

0	1"	2"	FILE
			S

NAME	B102.DWG	SHEET
SCALE	AS SHOWN	B10



HDR Engineering, Inc.
25 W. Cedar Street, Suite 200
Pensacola, FL 32502
Certificate of Authorization No. 4213



ISSUED FOR BID
NOT FOR CONSTRUCTION



## PORT OF PENSACOLA PAVING & RAIL REHABILITION PROJECT SOIL BORING LOGS (3 OF 4)

1" 2" FILENAME B103.DWG


SCALE AS SHOWN

SCALE AS SHOWN


SHEET

B103.

B103



HDR Engineering, Inc. 25 W. Cedar Street, Suite 200 Pensacola, FL 32502 Certificate of Authorization No. 4213





ISSUED FOR BID NOT FOR CONSTRUCTION




**PAVING & RAIL REHABILITION PROJECT** SOIL BORING LOGS (4 OF 4)

SHEET FILENAME | B104.DWG B104 SCALE AS SHOWN









PROJECT NUMBER 10419078 DESCRIPTION




1"	2"	FILENAME
		SCALE


ILENAME	X202.DWG	SHEET
SCALE	AS SHOWN	X20







Dist Time: Tuesday Ostaber 07 2025 - 8:20 mm Distad t



FILENAME | W201.DWG

SCALE AS SHOWN

W201

25 W. Cedar Street, Suite 200

Certificate of Authorization No. 4213

OCT. 2025


DATE


ISSUE


ISSUED FOR BID

DESCRIPTION

PROJECT NUMBER 10419078









#### NOTES:

- 1. HDPE JOINTS INSIDE CASING PIPE SHALL BE BUTT FUSED.
- 2. ENDS OF CASING PIPE SHALL BE SEALED WATER TIGHT DUE TO RESTRAINT SIZE IN ACCORDANCE WITH PROJECT SPECIFICATIONS.
- 3. CASING SPACERS TO BE INSTALLED IN ACCORDANCE WITH PROJECT SPECIFICATIONS. 4. ENDS OF CASING PIPE SHALL EXTEND MINIMUM 5' BEYOND EDGE OF OUTER RAIL.


#### JACK AND BORE DETAIL

NTS







TYPE 1 \*
FLAT-BOTTOM TRENCH. \*\* LOOSE BACKFILL.




TYPE 3
PIPE BEDDED IN 4-INCH MINIMUM LOOSE SOIL. \*\*\* BACKFILL LIGHTLY CONSOLIDATED TO TOP OF PIPE.



TYPE 5
PIPE BEDDED TO ITS CENTERLINE IN
COMPACTED GRANULAR MATERIAL, 4—INCH
MINIMUM UNDER PIPE. COMPACTED GRANULAR
OR SELECT MATERIAL\*\*\* TO TOP OF PIPE
(APPROXIMATELY 90% STANDARD PROCTOR,
AASHTO T—99).



TYPE 2
FLAT-BOTTOM TRENCH. \*\* BACKFILL LIGHTLY CONSOLIDATED TO CENTERLINE OF PIPE.




TYPE 4
PIPE BEDDED IN SAND, GRAVEL, OR
CRUSHED STONE TO DEPTH OF 1/8 PIPE DIAMETER, 4-INCH MINIMUM.
BACKFILL COMPACTED TO TOP OF
PIPE (APPROXIMATELY 80% STANDARD
PROCTOR, AASHTO T-99).

CONSIDERATION OF THE PIPE-ZONE EMBEDMENT CONDITIONS INCLUDED IN THIS FIGURE MAY BE INFLUENCED BY FACTORS OTHER THAN PIPE STRENGTH. FOR ADDITIONAL INFORMATION ON PIPE BEDDING AND BACKFILL, SEE ANSI/AWWA C600. \*FOR NOMINAL PIPE SIZES 14-INCH AND LARGER, \*\*FLAT BOTTOM IS DEFINED AS UNDISTURBED EARTH CONSIDERATION SHOULD BE GIVEN TO THE USE OF LAYING CONDITIONS OTHER THAN TYPE 1. \*\*\*"LOOSE SOIL" OR "SELECT MATERIAL" IS DEFINED AS "NATIVE SOIL EXCAVATED FROM THE TRENCH, FREE OF ROCKS, FOREIGN MATERIAL, AND FROZEN EARTH".

NOTE: TYPE 3 THROUGH TYPE 5 ARE ALLOWED ON THIS PROJECT. TYPE 1 AND TYPE 2 WILL NOT BE PERMITTED.

#### PIPE BEDDING AND BACKFILL



#### TYPICAL WATER MAIN INSTALLATION TRENCH DETAIL

NTS



24 0.250




			PROJECT MANAGER	HAC
			DESIGNED BY	EAF
			CHECKED BY	HAC
			DRAWN BY	WTP
			-	
			-	
			-	
Α	OCT. 2025	ISSUED FOR BID	-	
ISSUE	DATE	DESCRIPTION	PROJECT NUMBER	

ISSUED FOR BID NOT FOR CONSTRUCTION




#### PORT OF PENSACOLA **PAVING & RAIL REHABILITION PROJECT**

**NEW WATER LINES SECTIONS & DETAILS** 



2"	FILENAME	W501.DWG	SHEET
	SCALE	NTS	W501



SHEET

W502

FILENAME | W502.DWG

SCALE AS NOTED

HDR Engineering, Inc. 25 W. Cedar Street, Suite 200

Certificate of Authorization No. 4213


A OCT. 2025

DATE

ISSUED FOR BID

DESCRIPTION

PROJECT NUMBER




#### PIPE JOINT RESTRAINT TABULATION

SHOWING DISTANCES IN FEET FROM THE FITTING TO BE RESTRAINED TO THE LAST RESTRAINING GLAND REQUIRED


PIPE SIZE		HORIZONT	AL BENDS			EQUAL TEES
AND TYPE	90 Deg.	45 Deg.	22.5 Deg.	11.25 Deg.		See note 3
3" DI	18	8	4	2	33	1
4" DI	22	9	4	2	39	1
6" DI	31	13	6	3	55	1
8" DI	40	17	8	4	72	1
10" DI	48	20	9	5	86	1
12" DI	56	23	11	5	101	1
16" DI	70	29	14	7	129	1
20" DI	84	35	17	8	156	18
24" DI	96	40	19	9	181	41
4" PVC	28	12	6	3	62	1
6" PVC	39	16	8	4	87	1
8" PVC	50	21	10	5	114	1
10" PVC	60	25	12	6	136	1
12" PVC	70	29	14	7	160	1
16" PVC	88	36	17	9	205	1
20" PVC	105	43	21	10	247	29
24" PVC	120	50	24	12	287	64

NOTES: 1. Test pressure = 150 psi, soil group = SM, trench type = 3, depth = 2.5', safety factor = 2 2. Restrained lengths for vertical offsets, reducers & unequal size tees must be individually calculated. 3. With equal tees, the distances shown are with a run length of 40' as an example only. For other lengths and for unequal tees, individual calculations must be made.




RESTRAINED JOINTS







1. ONE LAYER OF #15 FELT TO BE USED TO PREVENT ADHESION OF CONCRETE TO FITTING.


- 2. ALL THRUST BLOCKS TO BE BACKED BY UNDISTURBED SOIL 3. THRUST BLOCK DIMENSIONS BASED ON SM SOIL CLASSIFICATION 4. CONCRETE MIN. 2,500 PSI.
- 5. JOINT RESTRAINTS ARE TO BE USED ON ALL FITTINGS. TRUST BLOCKS REQUIRED ON 90' BENDS, 45' BENDS, TEES, TAPPING



THURST BLOCKS








-1/2″ BEVEL

✓ 1/4" BEVEL



NTS

4 1/2" PUMPER CONN. TO FACE ROAD—

TYPICAL TAPPING SLEEVE


AND VALVE W/HYDRANT

OR D.I.P. SPOOLS (MIN 3" IN LENGTH)
WITH MEGALUG JOINT RESTRAINTS OR
APPROVED EQUAL. THRUST BLOCK FIRE HYDRANT

(TYP. OF 4)

TYPICAL TEE + VALVE

WITH HYDRANT



- COVER: SEE NOTE 2


45° BEND - M.J.

1 LAYER #15 FELT-

(TYPICAL)

CAST-IN PLACE COLLAR


24" PRE-CAST VALVE PAD 2" - 4" - J BRONZE DISC WITH VALVE INFO <u>--</u>∥--1/2" 4"THICK



#### NOTES:

- 1. VALVE BOX AND BOOT SHALL BE CAST IRON.
- 2. VALVE COVER SHALL BE MARKED "WATER" OR "SEWER" AS APPLICABLE 3. VALVE BOX TOP & COLLAR SHALL BE FLUSH WITH FINISHED GRADE OR
- ½" ABOVE NATURAL GROUND LEVEL. 4. GATE VALVE SHALL BE RESILIENT SEAT WITH MECHANICAL JOINT ENDS.
- 5. EARTH UNDER FLANGE OF VALVE BOX & COLLAR TO BE FIRM AND WELL TAMPED TO ENSURE AGAINST VALVE BOX SETTLING.





HDR Engineering, Inc. 25 W. Cedar Street, Suite 200 Pensacola, FL 32502 Certificate of Authorization No. 4213

NTS


			PROJECT MANAGER	HAC
			DESIGNED BY	EAF
			CHECKED BY	HAC
			DRAWN BY	WTP
			-	
			-	
			-	
Α	OCT. 2025	ISSUED FOR BID	-	
ISSUE	DATE	DESCRIPTION	PROJECT NUMBER	

**ISSUED FOR BID** NOT FOR CONSTRUCTION





#### PORT OF PENSACOLA **PAVING & RAIL REHABILITION PROJECT**

NEW WATER LINES SECTIONS & DETAILS



SHEET W504







PROJECT NUMBER 10419078 DESCRIPTION





SHEET	D200.DWG	ILENAME
D20	AS SHOWN	SCALE





ISSUED FOR BID

NOT FOR CONSTRUCTION

**PAVING & RAIL REHABILITION PROJECT** 

**DRAINAGE SYSTEM SECTIONS & DETAILS** 

FILENAME D500.DWG

SCALE AS SHOWN

SHEET

**D500** 

DESIGNED BY HAC

CHECKED BY HAC

PROJECT NUMBER 10419078

DRAWN BY PEM

Plot Time: Monday, October 06, 2025 — 6:32pm Plotted by: P


HDR Engineering, Inc. 25 W. Cedar Street, Suite 200

Certificate of Authorization No. 4213

A OCT. 2025

ISSUED FOR BID


DESCRIPTION





PROJECT NUMBER 10419078


DESCRIPTION


DATE













Certificate of Authorization No. 4213

PROJECT MANAGER HAC DESIGNED BY MLY CHECKED BY JLF DRAWN BY PEM A OCT. 2025 ISSUED FOR BID DESCRIPTION PROJECT NUMBER 10419078

ISSUED FOR BID NOT FOR CONSTRUCTION



# TRACK TURNOUT


#### PORT OF PENSACOLA **PAVING & RAIL REHABILITION PROJECT**


**TRACK 3 PROFILE** 


0 1"	2"	FILEI
		S

LEGEND:

FILENAME	R302.DWG	SHEET
	AS SHOWN	R30







HDR Engineering, Inc.
25 W. Cedar Street, Suite 200
Pensacola, FL 32502
Certificate of Authorization No. 4213

			PROJECT MANAGER	≀ HAC
			DESIGNED BY	/ MLY
			CHECKED BY	/ JLF
			DRAWN BY	/ PEM
				-
				-
				-
Α	OCT. 2025	ISSUED FOR BID		-
ISSUE	DATE	DESCRIPTION	PROJECT NUMBER	10419078

ISSUED FOR BID NOT FOR CONSTRUCTION




## PORT OF PENSACOLA PAVING & RAIL REHABILITION PROJECT

TRACK 6 PROFILE

1" 2"	FILENA
	SC

FILENAME	R305.DWG	SHEET
SCALE	AS SHOWN	R30



								PENSACOLA PO	RT TRACK 2										
CURVE NO.	DESC.	STATION	NORTHING	EASTING	BEARING	DISTANCE	RADIUS	DEGREE OF CURVE (CHORD)	Lc	DELTA	1	THETA	Ls	X	Υ	Ea (IN)	Eu (IN)	Vf (MPH)	Vp (MPH)
	РОВ	20+00.00	520408.0649	1113925.4346															
	PITO	20+29.99	520378.3923	1113929.7770															
					S 15°28'42" E	90.27													
	PC	21+20.25	520291.3950	1113953.8682															
CURVE 2-1	PI	23+42.15	520116.8993	1114082.8099			302.94	19°00'00"	443.79	83°56'05" LT						0.00	0.00	10	
	PT	25+64.05	520073.3816	1114295.3680															_
					N 80°35'12" E	387.95													
	POE	29+52.00	520136.8327	1114678.0954															

	PENSACOLA PORT TRACK 3																		
CURVE NO.	DESC.	STATION	NORTHING	EASTING	BEARING	DISTANCE	RADIUS	DEGREE OF CURVE (CHORD)	Lc	DELTA	1	THETA	Ls	X	Y	Ea (IN)	Eu (IN)	Vf (MPH)	Vp (MPH)
	РОВ	30+00.00	520103.3527	1114413.5857															
	PITO	30+29.99	520111.9031	1114442.3295															
					N 80°35'12" E	305.93													
	PC	33+35.92	520161.9390	1114744.1387															

								PENSACOLA PO	<b>RT TRACK 4</b>										
CURVE NO.	DESC.	STATION	NORTHING	EASTING	BEARING	DISTANCE	RADIUS	DEGREE OF CURVE (CHORD)	Lc	DELTA	1	THETA	Ls	X	Υ	Ea (IN)	Eu (IN)	Vf (MPH)	Vp (MPH)
	РОВ	40+00.00	520075.0172	1114305.2333															
	PITO	40+29.99	520079.9187	1114334.8071															
					N 73°26'02" E	181.74													
	PC	42+11.73	520131.7409	1114509.0185															
CURVE 4-1	PI	42+54.02	520142.5201	1114549.9013			674.69	08°30'00"	84.57	07°10'56" RT						0.00	0.00	10	
	PT	42+96.31	520150.7174	1114591.3790															
					N 80°29'45" E	152.53													
	POE	44+48.84	520175.9032	1114741.8161															

HDR Engineering, Inc.
25 W. Cedar Street, Suite 200
Pensacola, FL 32502
Certificate of Authorization No. 4213


			PROJECT MANAGER	HAC
			DESIGNED BY	MLY
			CHECKED BY	JLF
			DRAWN BY	PEM
			_	
			-	
			-	
Α	OCT. 2025	ISSUED FOR BID	-	
ISSUE	DATE	DESCRIPTION	PROJECT NUMBER	10419078

ISSUED FOR BID NOT FOR CONSTRUCTION



## PORT OF PENSACOLA PAVING & RAIL REHABILITION PROJECT

**GEOMETERY TABLE** 



FILENAME	R400.DWG
SCALE	AS SHOWN

SHEET **R400** 

me: Monday, October 06, 2025 — 6:59pm Plotted by: PMCINTIRE Ime: C:\pwworking\east01\d4343785\R400.dwg Layout Name: Layout1

A

								PENSACOLA PO	RT TRACK 6										
CURVE NO.	DESC.	STATION	NORTHING	EASTING	BEARING	DISTANCE	RADIUS	DEGREE OF CURVE (CHORD)	Lc	DELTA	1	THETA	Ls	X	Y	Ea (IN)	Eu (IN)	Vf (MPH)	Vp (MPH)
	РОВ	60+00.00	520800.7812	1114120.4704															
	PITO	60+18.37	520783.7626	1114127.3992															
					S 10°43'55" E	40.29													
	PC	60+58.66	520744.1791	1114134.9015															
CURVE 6-1	PI	60+67.56	520735.4148	1114136.4573			383.06	15°00'00"	17.81	02°39'48" RT						0.00	0.00	10	
	PT	60+76.47	520726.6155	1114137.8092															
					S 08°04'07" E	363.21													
	POE	64+39.68	520366.9957	1114188.7902															

								PENSACOLA PO	RT TRACK 7							_			
CURVE NO.	DESC.	STATION	NORTHING	EASTING	BEARING	DISTANCE	RADIUS	DEGREE OF CURVE (CHORD)	Lc	DELTA	1	THETA	Ls	X	Y	Ea (IN)	Eu (IN)	Vf (MPH)	Vp (MPH)
	РОВ	70+00.00	520857.2010	1114097.4998															
	PITO	70+18.37	520840.1825	1114104.4287															
					S 10°43'55" E	40.49													
	PC	70+56.86	520802.3711	1114111.5950															
CURVE 7-1	PI	70+65.74	520793.6316	1114113.1467			383.06	15°00'00"	17.75	02°39'19" RT						0.00	0.00	10	
	PT	70+74.61	520784.8585	1114114.4955															
					S 08°04'36" E	424.15			<u>-</u>								_		
	POE	74+98.76	520364.9211	1114174.0863															

HDR Engineering, Inc.
25 W. Cedar Street, Suite 200
Pensacola, FL 32502
Certificate of Authorization No. 4213

		PROJECT MANAGER	HAC
		DESIGNED BY	MLY
		CHECKED BY	JLF
		DRAWN BY	PEM
		-	
		-	
		-	
OCT. 2025	ISSUED FOR BID	-	
DATE	DESCRIPTION	PROJECT NUMBER	10419078
			DESIGNED BY CHECKED BY DRAWN BY  OCT. 2025 ISSUED FOR BID

ISSUED FOR BID
NOT FOR CONSTRUCTION



## PORT OF PENSACOLA PAVING & RAIL REHABILITION PROJECT


#### **GEOMETERY TABLE**


0	1"	2"	FILEN
			S


FILENAME	R401.DWG
SCALE	AS SHOWN


SHEET **R401** 


Name: C:\pwworking\east01\d4343785\R401.dwg Layout Name



































SHEET

P501

FILENAME P501.DWG

SCALE AS SHOWN

Plot Time: Wednesday, October 08, 2025 — 1:38pm Plotted by

HDR Engineering, Inc. 25 W. Cedar Street, Suite 200 Pensacola, FL 32502

Certificate of Authorization No. 4213


A OCT. 2025


DATE


ISSUED FOR BID


DESCRIPTION


PROJECT NUMBER 10419078














**S505** 

SCALE AS SHOWN

Pensacola, FL 32502

Certificate of Authorization No. 4213


A OCT. 2025

DATE

ISSUED FOR BID

DESCRIPTION

PROJECT NUMBER 10419078



ISSUED FOR BID

NOT FOR CONSTRUCTION

CATHODIC PROTECTION
BERTH 2 LANDSIDE SYSTEM REPAIRS

FILENAME CP100.DWG

SCALE AS SHOWN

**CP100** 

CHECKED BY HAC

PROJECT NUMBER | 10419078

DRAWN BY PEM

Plot Time: Monday, October 06, 2025 — 7:21pm Plotted by: PMC

HDR Engineering, Inc. 25 W. Cedar Street, Suite 200

Certificate of Authorization No. 4213

A OCT. 2025

DATE

ISSUED FOR BID

DESCRIPTION

Pensacola, FL 32502